

TC 5/101,Akkulam, Trivandrum-695017 +919961935096

Chempakam homes and interiors

Interior Consultant : Reshmi George

Mob :+ 91 9633693841

www.chempakamhomes.com chempakamtvm@gmail.com

		MOD :+ 91 9633693841						
.No		Description of Item	Unit	Qty	UNIT PRICE	AMOUNT	Total	
		M.BEDROOM 1						
,	A	KING SIZE COT (198x183 cm)	Nos	1	41900	41,900	_	
		Providing and fixing COT made of 303 BWR grade [century club prime] marine ply 16mm thick for boxing, 12mm thick 303 BWR grade [century club prime] marine ply for top .The external surface finished with 0.8/1 mm thick laminate and internal surface finished with 0.7mm thick white laminate with all necessary hardwares.						
	В	HEADER UNIT (200x90 cm)	Nos	1	16500	16,500		
		Providing and Fixing HEAD BOARD made of 16 mm thick 303 grade BWR [century club prime] marine ply with ,0.8/1mm & 0.7mm thick laminate is hot pressed on both sides with matching 0.8mm edge band with all necessary hardwares.						
(С	SIDE TABLE (40x40 cm)	nos	1	7850	7,850		
		Providing and fixing SIDE TABLE – Boxing and Partition made of 16 mm thick 303 grade BWR [century club prime] marine ply with ,0.8/1mm & 0.7mm thick laminate is hot pressed on both sides Shutter, partition and box edges covered with 0.8 mm PVC edge bands. Hinges and handles (hettich) are provided.						
ι	D	4 DOOR WARDROBE (160X210 cm)	Sqft	36	1800	64,800		
		Providing and fixing WARDROBE - Boxing, Partition and shutters are made of 16MM thick 303 grade(century culb prime) marine ply with outside face.8/1mm thick Laminated and inside face 0.7mm thick white laminate. shutter, box, and partition edges covered with 0.8mm PVC edge bands .6mm multiwood[Thomson] back panelling is provided. Hinges, 8 inch Handles and Sliders(hettich) are provided.	ee edge			-		
	Ε	DRESSING UNIT WITH MIRROR (40x210cm)	Nos	1	12500	12500	-	
		Providing and fixing DRESSING UNIT - Partition(ledge) is made of 16MM thick 303 grade(century culb prime) marine ply with outside face.8/1mm thick Laminated and inside face 0.7mm thick white laminate. edges covered with PVC edge bands and 5 mm thick mirror fixed using mirror spacer on wall.(mirror size 40x150 cm).						
	F	WORKING TABLE (100x 60 cm)	Nos	1	15000	15000		
		Providing and fixing WORKING TABLE - Boxing, Partition and shutters are made of 16 mm thick 303 grade BWR [century club prime] marine ply with 0.8/nmm & 0.7mm thick laminate is hot pressed on both sides Shutter, partition and box edges covered with PVC edge bands. Hinges and handles are provided(hittich)						
	G	LEDGE	Nos	1	3500	3,500		
2 _		BEDROOM 2						
	Α	KING SIZE COT (198x183 cm)	N	os 1	41,900	41,900		
		Providing and fixing COT made of 303 BWR grade [century club prime] marine ply 16mm thick for boxing, 12mm thick 303 BWR grade [century club						

		prime] marine ply for top .The external surface finished with 0.8/1 mm thick laminate and internal surface finished with 0.7mm thick white laminate with all					
	В	necessary hardwares.	Maa	1	16500	16.500	
	В	Providing and Fixing HEAD BOARD made of 16 mm thick 303 grade BWR [century club prime] marine ply with ,0.8/1mm & 0.7mm thick laminate is hot pressed on both sides with matching 0.8mm edge band with all necessary hardwares.	Nos	1	16500	16,500	_
	С	SIDE TABLE (40x40 cm)	Nos	1	7,850	7,850	
		Providing and fixing SIDE TABLE – Boxing and Partition made of 16 mm thick 303 grade BWR [century club prime] marine ply with ,0.8/1mm & 0.7mm thick laminate is hot pressed on both sides Shutter, partition and box edges covered with 0.8 mm PVC edge bands. Hinges and handles (hettich) are provided.					1,45,850.00
	D	3 DOOR WARDROBE (120X210 cm)	Sqft	27	1800	48,600	
		Providing and fixing WARDROBE - Boxing, Partition and shutters are made of 16MM 303 grade(century culb prime) marine ply with outside face.8/1mm thick Laminated and inside face 0.7mm thick white laminate. shutter, box, and partition edges covered with 0.8mm PVC edge bands. 6mm multiwood[Thomson] back panelling is provided . Hinges, 8 inch Handles and Sliders(hettich) are provided.					
		DRESSING UNIT WITH MIRROR (40x210cm) Providing and fixing DRESSING UNIT - Partition(ledge) is made of 16MM thick 303 grade(century culb prime) marine ply with outside face.8/1mm thick	Nos	1	12500	12,500	
		Laminated and inside face 0.7mm thick white laminate. edges covered with PVC edge bands and 5 mm thick mirror fixed using mirror spacer on wall.(mirror size 40x150 cm)					
	F	WORKING TABLE (100x60cm)	Nos	1	15000	15,000	
		Providing and fixing WORKING TABLE - Boxing, Partition and shutters are made of 16 mm thick 303 grade BWR [century club prime] marine ply with ,0.8/nmm & 0.7mm thick laminate is hot pressed on both sides Shutter , partition and box edges covered with PVC edge bands. Hinges and handles are provided(hittich)					
	G	LEDGE	Nos	1	3500	3500	
3		MODULAR KITCHEN CABINETS					
	Α	MODULAR CABINETS (L-SHAPE)					
		Providing and fixing MODULAR CABINETS – box,shutters and partition is made of 16mm thick 710 BWP grade [century club prime] marine plywood . 0.8/1mm & 0.7mm thick laminate is hot pressed on both sides. Provided all necessary hardware's. Shutters and box edges covered with PVC edge bands. 6mm multiwood back panelling is provided. Hinges and sliders are provided(hettich) • Normal handle 14 nos (hettich)					97,500.00
	*	Bottom Cabinet (304x85cm)	Sqft	29	1950	56,550	
	*	Top Cabinet (304x60cm)	Sqft	21	1950	40,950	
4		DINING AREA	_				
A	A	WASH COUNTER(100X60)	nos	1	16000	16000	
		Providing and fixing WASH COUNTER – Boxing, shutters and Partition are made of 16MM thick 710 grade [century ply prime] BWP marine plywood with ,0.8/1mm & 0.7mm thick laminate is hot pressed on both sides Partition, Box and Shutter edges covered with PVC edge bands. 6mm multiwood[Thomson] back panelling is provided . Hinges, Handles and Sliders(hettich) are provided.					
В	3	MIRROR	nos	1	2,500	2,500	55,550.00
		Providing and fixing 4mm side polished mirror using mirror spacer on wall.					
С	C	CROCKERY UNIT TOP UNIT-120X75 cm BOTTOM UNIT-120X75 cm	Sqft	19	1950	37,050	

		Providing and fixing CROCKERY - Boxing, Partition and shutters are made of 16MM thick 303 grade [century club prime] BWP marine plywood with 0.8/1 mm & 0.7 mm thick laminate is hot pressed on both sides and shutters include 4 mm thick plane glass .partition box edges covered with PVC edge bands. 6mm multiwood[Thomson] back panelling is provided .Hinges and Handles (hettich) are provided.							
5		LIVING AREA							
	A	T V UNIT							
	*	Bottom unit	nos	1	19000	19000			
		Providing and fixing TV Unit - box partition and Shutters are made of 16MM thick 303 grade [century club prime] BWP marine plywood with 0.8/1 mm & 0.7 mm thick laminate is hot pressed on both sides Provided all necessary hardwares. Shutters and box edges covered with PVC edge bands. 6mm multiwood[Thomson] back panelling is provided .Hinges and Handles are provided(HETTICH)	,			39,500.00			
	*	LEDGE	nos	2	3,500	7,000			
		Providing and fixing LEDGE as per design - made of 16MM thick 303 grade BWR [century club prime]marine ply with 0.8/1 mm & 0.7 mm thick laminate is hot pressed on both sides .Edges are covered with PVC edge bands.				1			
	В	NORMAL GYPSUM FALSE CIELLING (150 SQFT)	sqft	150	90	13,500			
5		EXTRA WORK							
	Α	KITCHEN ACCESSORIES (HETTICH)							
	*	Cutlery tray (90 cm)	Nos	1	1488	18,000	18,000		
	*	Cup and Soucer basket (60cm)	Nos	1	4119				
	*	Glass tray Plate tray and dip tray (90cm)	Nos	1	7424				
	*	Plain Basket (6" 90cm)	Nos	1	4297				
	*	Prolift (10kg)	Nos	1	336	-			
					Amount	5,18,450.00			
			GRAND TOTAL						
						Gst(185 extra)	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
		MATERIALS USED : Plywood used : 710 BWP Marine grade plywood 303BWR Marine grade plywood							
		Accessories :Hettich Hinges & Sliders-Regular : For all units (non soft close)							
TERMS AND CONDITIONS * This estimate is based on the plan received ,which will be finalised only after site measurements.									
		* Any deviation from this quotation will attract rate changes.							
		* Electricity and water needed for the project should be supplied by the client at free of cost. In case of power failure, client needs to arrange the altern Power (Generator). Covered and secure space for keeping our materials and machines at site should be provided free ofcost *This estimate validity is for 30 days							
		PAYMENT TERMS							
		* Token :2D and 3D Designing willbestarted	5%						

60%

30% 5%

ESTIMATE EXCLUDES

* Final Payment:AfterCompletion

Demolishing and waste disposal , electrical work , granite slab , plumbing work .

 * Part Payment :While delivering units at site (Installation will bestarted on Receipt of this)

* Advance :Work execution will be startedatfactory